

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-22747-00-00
Spot: NWSENE Sec/Twnshp/Rge: 29-30S-7E
3568 feet from S Section Line, 1164 feet from E Section Line
Lease Name: STOLP Well #: 14
County: COWLEY Total Vertical Depth: 2907 feet

Operator License No.: 9576
Op Name: WHITEMAN, RON DBA GEN-DOR OIL C.
Address: 8135 281ST RD
CAMBRIDGE, KS 67023

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2906		50 SX
SURF	8.625	208		140 SX

94.48

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/17/2007 8:00 AM
Plug Co. License No.: 9576 Plug Co. Name: WHITEMAN, RON DBA GEN-DOR OIL CO.
Proposal Rcvd. from: RONNIE WHITEMAN Company: GEN-DOR OIL CO. Phone: (620) 467-2615

Proposed Plugging Method: FILL BOTTOM OF HOLE W/SAND TO 50' ABOVE PERFS DUMP BAIL 6 SXS CEMENT ON TOP. PULL PIPE, CIRCULATE CEMENT FROM 350'. RIH W/TBG TAG BOTTOM PLUG, PRODUCTION CASING HAS ALREADY BEEN PULLED.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/17/2007 12:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

12-17-2007, RIH W/TBG TO TAG BOTTOM PLUG, CIRCULATED HOLE CLEAN @ 755'. SHUT DOWN. 12-18-2008, TBG STACKED OUT @ 1475', TAGGED SOLID, GOT BACK INTO CUT CSG, RAN TBG TO 2870', 19' OFF BOTTOM. 12-19-2007, W/TBG @ 2850', GEN-DOR MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL, FLUIDS CIRCULATED @ SURFACE DURING CEMENT JOB. PULLED TBG @ 350', GEN-DOR OIL CO. MIXED & PUMPED 140 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 1230 PM 12-17-2007. UNITED CEMENTING TICKET #8076. 1475' OF 4-1/2" CSG WAS PULLED FROM THIS WELL.

Perfs:

Top	Bot	Thru	Comments
2874	2884		
2864	2870		

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 28 2008
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 1-30-08
INV. NO. 2008061129

Remarks: -096.68023,37.41303, PERFS 2864'-2884'

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

PKT