

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23457-00-00
Spot: NESWNE Sec/Twnshp/Rge: 29-30S-7E
3565 feet from S Section Line, 1809 feet from E Section Line
Lease Name: STOLP Well #: 15
County: COWLEY Total Vertical Depth: 2940 feet

Operator License No.: 9576
Op Name: WHITEMAN, RON DBA GEN-DOR OIL C
Address: 8135 281ST RD
CAMBRIDGE, KS 67023

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2940		50 SX
SURF	8.625	343		130 SX

95.55

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/10/2007 8:00 AM
Plug Co. License No.: 9576 Plug Co. Name: WHITEMAN, RON DBA GEN-DOR OIL CO.
Proposal Rcvd. from: RONNIE WHITEMAN Company: GEN-DOR OIL CO. Phone: (620) 467-2615

Proposed Plugging Method: FILL BOTTOM OF HOLE W/SAND TO 50' ABOVE PERFS DUMP BAIL 6 SXS CEMENT ON TOP, PULL PIPE, CIRCULATE CEMENT FROM 395'. RIH W/TBG TAG BOTTOM PLUG, PRODUCTION CASING HAS ALREADY BEEN PULLED.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/13/2007 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

12-10-2007, RIH W/TBG TO TAG BOTTOM PLUG, TBG STACKED OUT @ 1380'. TAGGED SOLID, COULD NOT GET BACK INTO CUT CSG. 12-13-2007, W/TBG @ 1365', GEN-DOR MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL, FLUIDS CIRCULATED @ SURFACE DURING CEMENT JOB. PULLED TBG @ 405', GEN-DOR OIL CO. MIXED & PUMPED 141 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 1700 PM 12-13-2007. UNITED CEMENTING TICKET #8073. 1380' OF 4-1/2" CSG WAS PULLED FROM THIS WELL.

Perfs:

Top	Bot	Thru	Comments
2888	2891		
2881	2885		

INVOICED

DATE 1-30-08

INV. NO. 2008061129

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 28 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: -096.68245,37.41302, PERFS 2881'-2891'

Plugged through: TBG

District: 02

Signed _____

Duane Krueger

(TECHNICIAN)

PKT