

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-19230-00-00  
Spot: SWNWSE Sec/Twnshp/Rge: 19-32S-3E  
1692 feet from S Section Line, 2521 feet from E Section Line  
Lease Name: WAITE Well #: 4  
County: COWLEY Total Vertical Depth: 3600 feet

Operator License No.: 33608  
Op Name: W.D. SHORT OIL CO., LLC  
Address: 102 S RIVER RD PO BOX 729  
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	20	42		
PROD	5.5	3549		200 SX
SURF	8.25	2615		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/02/2006 11:00 AM  
Plug Co. License No.: 33608 Plug Co. Name: W.D. SHORT OIL CO., LLC  
Proposal Rcvd. from: MIKE ANSTINE Company: W D SHORT OIL CO LLC Phone: (620) 455-3576

Proposed Plugging Method: CASING IS PARTED @ 1850', REMOVE 5-1/2" CSG @ 1850', CAN NOT GET BACK INTO 5-1/2" CSG. PUMP 100 SXS CEMENT, PULL STRINGS OF CASING AND SET PLUGS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 02/02/2006 1:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

*1/2/08 KCC PRT per Dist.*

CIBP @ 3440' W/200 SXS, CIBP @ 3452', 3470', 3502'. 5-1/2" CASING PARTED @ 1850', LAYED DOWN 5-1/2" CASING. CAN NOT GET BACK INTO 5-1/2" CSG FOR BOTTOM PLUG. RIH W/TBG @ 1850', CONSOLIDATED 10" CASING @ 350', LAYED DOWN 10" CSG. 02-02-2008, RIH W/TBG @ 350', CONSLIDATED MIXED & PUMPED 525 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 1300 PM 2-2-2008. CONSLIDATED CEMENT TICKET #13388.

Perfs:

Top	Bot	Thru	Comments
3430	3436		
3083	3090		
3022	3027		

**INVOICED**

DATE 1-30-08  
INV. NO. 2008-061143

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 24 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks: -097.14030,37.25016, PBTD 3400' PERF 3022-27, 3083-90, 3430-36

Plugged through: TBG

District: 02

Signed

*Duane Krueger*

(TECHNICIAN)

*PRT*