

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

RECEIVED

Form CP-1
September 2003

WELL PLUGGING APPLICATION

JAN 11 2008

This Form must be Typed
Form must be Signed
All blanks must be Filled

Please TYPE Form and File ONE Copy

CONSERVATION DIVISION
WICHITA, KS

API # 15-05500855-055-21590-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date December 14, 1997

Well Operator: EXCO Resources, Inc. KCC License #: 32581
(Owner/Company Name) (Operator's)

Address: P.O. Box 1227 City: Woodward

State: Oklahoma Zip Code: 73802 Contact Phone: (580) 256-2613 Ext. 201

Lease: Huston Well #: 1-24R Sec. 24 Twp. 24 S. R. 32 East West

SE - SE - SE - NW/4 Spot Location / QQQQ County: Finney

1320 3930 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1290 4002 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 520' Cemented with: 250 Sacks

Production Casing Size: 5 1/2" Set at: 2808' Cemented with: 295 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perforation 4/SPF @ 2626' to 2638', 48 holes, no bridge plug
or CIBP has been set above perfs.

Elevation: 2892' (G.L. / K.B.) T.D.: 2805' P.B.T.D.: 2801' Anhydrite Depth: 1875'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Shot fluid level down 5 1/2" @ 2076' from
surface. Pump 300 lbs. cotton seed hulls and 250 sks. 60/40 Pozmix w/6% Gel down 51/2"
casing to fill to surface. Attempt to pump 100 sks. cement down annulus. Cut off 8 5/8"
and 5 1/2" casing 4' below ground level and capped wellbore with metal I.D. marker.

Is Well Log attached to this application as required? Yes No Is ACO-1 filled? Yes No

If not explain why? EXCO Resources is trying to get a copy of the open hole logs.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Mike Lemieux

Phone: (620) 655-2007

Address: P.O. Box 729 City / State: Beaver, Oklahoma 73932

Plugging Contractor: EXCO Resources, Inc. KCC License #: 32581
(Company Name) (Contractor's)

Address: P.O. Box 1227, Woodward, OK 73802 Phone: (580) 256-2613 Ext. 201

Proposed Date and Hour of Plugging (if known?): January 10, 2008 at 0900 Hrs.

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: January 7, 2008 Authorized Operator / Agent: [Signature] EXCO General Superintendent D & P
(Signature)

Mall to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*well plugged - KCC-Dlg

Dist
01