

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

NOV 05 2007

CONSERVATION DIVISION  
WICHITA, KS

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Tri United, Inc.  
Address: 950 270th ave Hays, Ks 67601  
Phone: (785) 628 3670 Operator License #: 03194  
Type of Well: D & A (OWWO) Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: August 30th 2007 (Date)  
by: Herb Deines (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Arbuckle Depth to Top: 3577 Bottom: 4074 T.D. 4074  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-051-03527-00-02 <sup>KCC</sup> <sup>ap.</sup>  
Lease Name: Vine-Sook  
Well Number: #5  
Spot Location (QQQQ): E/2 - SW - NE  
3300 Feet from  North /  South Section Line  
1650 Feet from  East /  West Section Line  
Sec. 26 Twp. 11 S. R. 19  East  West  
County: Ellis  
Date Well Completed: Never Reached desired TD 8-29-07  
Junk in hole. Total depth 620'  
Plugging Commenced: 9-6-2007 11:00 AM  
Plugging Completed: 9-6-2007 12:30 PM

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		old Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
LKC 3291'	shale, lime stone	160'	surface	8 5/8	160'	none
		3630'	Surface	5 1/2	3630'	none
Arb 3577'	Dolomite					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Ran 2" tubing to total depth reached by our reentry of old well. (620')  
Pumped cement through tubing circulated it to the surface 70sks 60/40  
pulled tubing out of hole, Filled original 5 1/2 full 10 sks cement.  
Tyed on Annulus pumped cement in pressured up to 300# State plugger on locatic

Name of Plugging Contractor: Allied Cementing/Tri united, Inc License #: 03194 <sup>Pat Staab</sup>  
Address: (50 270th Ave Hays, Ks 67601

Name of Party Responsible for Plugging Fees: Tri United, Inc. 950 270th Ave Hays, Ks 67601  
State of Kansas County, Ellis, ss.

Eugene Leiker (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Eugene E Leiker  
(Address) \_\_\_\_\_



DESCRIBED and SWORN TO before me this 2nd day of Nov., 2007  
Roberta Angel My Commission Expires: 10-24-08  
Notary Public

# ALLIED CEMENTING CO., INC.

33159

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: Passo

API-15-051-03527-00-01

DATE <u>9-6-07</u>	SEC <u>26</u>	TWP. <u>11</u>	RANGE <u>19</u>	CALLED OUT	ON LOCATION <u>11:00 AM</u>	JOB START	JOB FINISH <u>12:30 PM</u>
LEASE <u>Vine</u>	WELL # <u>5</u>	LOCATION <u>HAYEN 4W 5N</u>			COUNTY <u>Ellis</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD OR NEW <small>(Circle one)</small>							

CONTRACTOR Co Tools

TYPE OF JOB Plug

HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_

CASING SIZE 5 1/2 DEPTH \_\_\_\_\_

TUBING SIZE 2 3/8 DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT \_\_\_\_\_

OWNER \_\_\_\_\_

CEMENT AMOUNT ORDERED 80pk 60/40-4

COMMON	<u>48</u>	@	<u>11.10</u>	<u>532.80</u>
POZMIX	<u>32</u>	@	<u>6.20</u>	<u>198.40</u>
GEL	<u>3</u>	@	<u>16.65</u>	<u>49.95</u>
CHLORIDE		@		
ASC		@		
<b>RECEIVED</b>				
KANSAS CORPORATION COMMISSION				
@				
@ <b>NOV 05 2007</b>				
@ CONSERVATION DIVISION				
@ WICHITA, KS				
@				
@				
HANDLING	<u>83</u>	@	<u>1.90</u>	<u>157.20</u>
MILEAGE	<u>SK/mi/09</u>			<u>224.10</u>
				TOTAL <u>1162.95</u>

**EQUIPMENT**

PUMP TRUCK CEMENTER Bill

# 409 HELPER CRAB

BULK TRUCK

# 410 DRIVER Doug

BULK TRUCK

# \_\_\_\_\_ DRIVER \_\_\_\_\_

**REMARKS:**

Job c 620' Circ Cement

w/ 80pk

pull tubing

Fill csg w/ 10pk Full

Pump down Ann 300 OK

**SERVICE**

DEPTH OF JOB				
PUMP TRUCK CHARGE				<u>720.00</u>
EXTRA FOOTAGE		@		
MILEAGE	<u>30</u>	@	<u>6.00</u>	<u>180.00</u>
MANIFOLD		@		
		@		
		@		
				TOTAL <u>900.00</u>

CHARGE TO: TR: United Inc

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

state Rep on location  
(PAT Staab)

**PLUG & FLOAT EQUIPMENT**

_____	@	_____	_____
_____	@	_____	_____
_____	@	_____	_____
_____	@	_____	_____
_____	@	_____	_____
TOTAL _____			

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE Eugene E. Wilson

PRINTED NAME \_\_\_\_\_