

15-163-00385-00-00
WELL PLUGGING RECORD

STATE OF KANSAS
 STATE CORPORATION COMMISSION

Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 800 Bittling Building
 Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
 when reporting plug-
 ging off formations.

Rooks County, Sec. 26 Twp. 10s Rge. (E) 20 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE $\frac{1}{4}$ -NW $\frac{1}{4}$ -NW $\frac{1}{4}$ -

Lease Owner Champlin Refining Company

Lease Name M. Annon Well No. 1

Office Address P.O. Dr. #552, Enid, Oklahoma.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 10, 1951

Application for plugging filed December 10, 1951

Application for plugging approved December 9, (Verbal) 1951

Plugging commenced December 10, 1951

Plugging completed December 10, 1951

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas.

Producing formation Depth to top Bottom Total Depth of Well 3870' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8" OD	144'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3870' TD to 140' and set plug and pumped in 15 sacks of cement on top of plug then filled hole with heavy mud from top of cement to 40' and dumped in 1/2 sack of hulls and pumped in 10 sacks of cement filling hole to bottom of cellar.

FILED
 DEC 26 1951
 12-26-1951

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Champlin Refining Company
 Address P. O. Dr. #552, Enid, Oklahoma.

STATE OF Kansas, COUNTY OF Barton, ss. S. P. Hall (employee of owner) or (owner) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. P. Hall
P. O. Box 167
Ellinwood, Kansas. (Address)

SUBSCRIBED AND SWORN TO before me this 19th day of December, 19 51

My commission expires September 10, 1955 N. Kenneth Stevin Notary Public.

22-2625 2-48-15M

PLUGGING
 FILE NO. 2610 R 200
 BOOK 131 LINE 8

15-163-00385 00-00

M. ANNON #1

990' from the North line (FNL)
and 990' from the West line (FWL)
of the Northwest Quarter (NW/4) of
Section Twenty-six, Township Ten
South (10S), Range Twenty West (20W),
Rooks County, Kansas.

Formation Log

0'	- 144'	Sand & shale
144'	- 500'	Shale
500'	- 1060'	Shale, sand & shells
1060'	- 1665'	Shale & sand
1665'	- 2520'	Shale & anhydrite
2520'	- 2750'	Shale & lime
2750'	- 2855'	Lime & shale
2855'	- 3050'	Shale & lime
3050'	- 3115'	Lime & shale
3115'	- 3370'	Shale & lime
3370'	- 3485'	Lime & shale
3485'	- 3630'	Lime
3630'	- 3670'	Lime & shale
3670'	- 3750'	Lime
3750'	- 3778'	Conglomerate
3778'	- 3791'	Conglomerate & lime
3791'	- 3870'	Lime
3870'	- Total	Depth

STATE OF KANSAS
DEPARTMENT OF GEOLOGY

DEC 26 1957

12-26-1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING

FILE SEC 26 T 10 R 20W
BOOK PAGE 13 LINE 8