

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: McCoy Petroleum Corporation

Address: 8080 E. Central, Suite #300, Wichita, KS 67206-2366

Phone: 316-636-2737 x 104 Operator License # 5003

Type of Well: Oil & Gas KCCPKT Per CP2/3 Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Morrow Depth to Top: 5300 Bottom: 5304 T.D. 5782
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number 15-175-21184-00-00

Lease Name: ROONEY "A" #1-18 KCCPKT

Well Number: #1-18 Per CP2/3

Spot Location (QQQQ): C NE SW

1980 Feet from North / South Section Line

3300 Feet from East / West Section Line

Sec 18 Twp 31 S. Rng. 34W East West

County: Seward

Date Well Completed: 6/8/91

Plugging Commenced: 1/2/08

Plugging Completed: 1/3/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				20"	None	None
				8 5/8"	1738'	None
				4 1/2"	5782'	2060'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1/2/08: MIRU. Pulled 170 jts of 2 3/8" tubing. Pumped 200# hulls and 40 sacks cement down 4 1/2" casing. Displaced to 5000'. Max pressure was 400#. Shut in 250#. Ripped casing at 2060' and came free. Pulled casing up to 1800'. Pumped 15 gel, 50 sacks cement. Pulled to 900' and pumped 50 sacks cement. Pulled to 40' and pumped 20 sacks cement to surface. Total cement was 120 sacks of 60/40 pozmix.


Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925 RECEIVED KANSAS CORPORATION COMMISSION

Address: 190 US Highway 56, Ellinwood, KS 67526 JAN 23 2008

Name of Party Responsible for Plugging Fees: McCoy Petroleum Corporation CONSERVATION DIVISION WICHITA, KS

State of Kansas County, Sedgwick, ss.

Scott Hampel - Employee of Operator (Employee of Operator) or (Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Scott Hampel

(Address) 8080 E. Central, Suite #300, Wichita, KS 67206-2366

SUBSCRIBED and SWORN TO before me this 22nd day of January 20 08

Brent B Reinhardt My Commission Expires: 12/7/2011
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT