

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: McCoy Petroleum Corporation
Address: 8080 E. Central, Suite #300, Wichita, KS 67206-2366
Phone: 316-636-2737 x 104 Operator License # 5003

API Number 15-055-21577 - 00-00
Lease Name: YEISER "A" #2-4 KCCPKT PEN
Well Number: #2-4 CP 2/3

Type of Well: Oil & Gas PRCPT 2/3 PKTKCC Docket #:
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

Spot Location (QQQQ): C NW SE

The plugging proposal was approved on: (Date)

1980 Feet from [] North / [X] South Section Line

by: Steve Durrant (KCC District Agent's Name)

1980 Feet from [X] East / [] West Section Line

Is ACO-1 filed? [X] Yes [] No If not, is well log attached? [] Yes [X] No

Sec 4 Twp 26s S. Rng. 34w [] East [X] West

Producing Formation(s): List All (If needed attach another sheet)

County: Finney

Morrow Depth to Top: 4849 Bottom: 4854 T.D. 5135
Mississippian Depth to Top: 5034 Bottom: 5124 T.D. 5135

Date Well Completed: 10/7/97

Plugging Commenced: 1/10/08

Plugging Completed: 1/11/08

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Rows show casing records for 20", 8 5/8", and 4 1/2" sizes.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

1/2/08: MIRU. Cut surface off 4' below ground. Tied on to 4 1/2" casing. Pumped 200# hulls and 40 sacks cement down 4 1/2" casing. Displaced to 4250". Ripped casing at 2440'. Worked pipe free. Pulled casing up to 1620. Pumped 10 gel, 50 sacks cement at 1620'. Pulled to 900' and pumped 50 sacks cement. Pulled to 40' and pumped 20 sacks cement to surface. Total cement was 120 sacks of 60/40 pozmix.

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

JAN 23 2008

Address: 190 US Highway 56, Ellinwood, KS 67526


CONSERVATION DIVISION
WICHITA, KS

Name of Party Responsible for Plugging Fees: McCoy Petroleum Corporation

State of Kansas County, Sedgwick, ss.

Scott Hampel - Employee of Operator (Employee of Operator) or (Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature of Scott Hampel



(Signature) _____

(Address) 8080 E. Central, Suite #300, Wichita, KS 67206-2366

SUBSCRIBED and SWORN TO before me this 22nd day of January 20 08

Brent B Reinhardt My Commission Expires: 12/7/2011
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202