

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

JAN 31 2008

CONSERVATION DIVISION
WICHITA, KS

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

Lease Operator: Shakespeare Oil Company, Inc.

Address: 202 West Main Street, Salem, IL 62881

Phone: (618) 548-1585 Operator License #: 7311

Type of Well: Oil D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 12/22/07 (Date)

by: Ed Schumacher (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)
N/A Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 109-20795 - - 00 00

Lease Name: P. Scheetz

Well Number: 1-16

Spot Location (QQQQ): E/2 - SW - SW - SE
367 Feet from North / South Section Line

2133 Feet from East / West Section Line

Sec. 16 Twp. 13S S. R. 32 East West

County: Logan

Date Well Completed: 12/22/07

Plugging Commenced: 12/22/07

Plugging Completed: 12/22/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	223'	8 5/8"	223'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rotary mud from 4679' to 2515', 2390' to 1490', 990' to 275' and 75' to 40'.

Cement plugs from 2515' to 2390', 1490' to 990', 275' to 75', 40' to 0', 15 sx rathole, 10 sx mousehole.

A total of 200 sx 60/40 Pozmix w/ 4% gel & 1/4# Flo-seal was placed by drillpipe and cemented by Allied Cementing Co.

Name of Plugging Contractor: Murfin Drilling Co. Rig #14 License #: 30606


Address: 250 N. Water, Suite 300, Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Shakespeare Oil Company, Inc.

State of Illinois County, Marion, ss.

Donald R. Williams, Vice President (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Donald R. Williams

(Address) 202 West Main Street, Salem, IL 62881

SUBSCRIBED and SWORN TO before me this 28th day of January, 2008

Melissa A. Noel My Commission Expires: 11-6-11
Notary Public