

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: John Roy Evans  
Address: P.O. Box 385, Claflin, KS 67525  
Phone: (620) 587-3565 Operator License #: 7030  
Type of Well: oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 09-21-07 (Date)  
by: Steve Bond (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Arbuckle Depth to Top: 3334 Bottom: \_\_\_\_\_ T.D. 3341  
Kansas City Depth to Top: 3093 Bottom: 3280 T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-009-20955-00-00  
Lease Name: Hitschmann  
Well Number: 1  
Spot Location (QQQQ): \_\_\_\_\_ - NW - SW - SW  
990 Feet from  North /  South Section Line  
330 Feet from  East /  West Section Line  
Sec. 33 Twp. 17 S. R. 12  East  West  
County: Barton  
Date Well Completed: 10/13/75  
Plugging Commenced: 12/7/07  
Plugging Completed: 12/10/07

PTT  
KCC  
Per  
CP-43

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		235'	surface	8 5/8"	10/13/75	
		3337'	surface	4 1/2"	10/19/75	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Dug out cellar & found 8 5/8" surface pipe orange peeled to 4 1/2" csg. Welded 2" collar into 8 5/8" to check backside squeeze with cement pump truck. Ran in 2100' 2 3/8" tubing. Cemented with 125 sacks 60/40 Pozmix with 400# hulls. Pulled up to 1000' & cemented with 175 sacks 60/40 pozmix with 200# hulls. Cement wouldn't circulate to surface. It held 500 psi. Dug out cellar and found 8 5/8" urface pipe orange peeled to 4 1/2" csg. Welded 2" collar into 8 5/8" to check backside squeeze with cement pump truck. Ran in 2100' 2 3/8" tubing. Cemented with 125 sacks 60/40 Pozmix with 400# hulls. Pulled up to 1000' & cemented with 175 sacks 60/40 Pozmix with 200 # hulls. Cement wouldn't circulate to surface. Checked backside for squeeze; it held 500 psi. Pulled tubing out for weekend. On 12/17/07 ran in 2 3/8" tubing & tagged @ 1065'. Pumped cement @ 960'. Pumped 110 sacks 60/40 Pozmix with 400 # hulls. Cement did circulate to surface. Hooked up to back side & mixed 5 sacks cement & pumped to 100 psi & shut in. Hooked to 4 1/2" csg & pumped to 100 psi & shut in.

Name of Plugging Contractor: Express Well Service & Supply, Inc. License #: 6426  
Address: Box 19, Victoria, KS 67611-0019

RECEIVED  
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: John Roy Evans  
State of Kansas County, Barton, ss.

JAN 29 2008

Gary Kirmer (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

CONSERVATION DIVISION

(Signature) [Signature]  
(Address) Gary Kirmer, P.O. Box 536, Claflin, KS 67525 (620)-793-2026

SUBSCRIBED and SWORN TO before me this 28 day of January, 20 08  
[Signature] Notary Public My Commission Expires: 9-30-2011

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten mark]