

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: The Bill Bowman Oil Company

Address: 2640 W Road

Phone: (785) 885-4830 Operator License #: 33263

Type of Well: Oil DH KCCPT per CP2/3 Docket #: N/A
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: January 9, 2008 (Date)

by: Rich Williams District #4 (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

Arbuckle Depth to Top: 3649' Bottom: 3661' T.D. 3661'

(Dry Hole) Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-051-25706-0000

Lease Name: GSL

Well Number: #2

Spot Location (QQQQ): _____ - S/2 - S/2 - N/2

2200 Feet from North / South Section Line

2640' Feet from East / West Section Line

Sec. 35 Twp. 11S S. R. 18 East West

County: Ellis County, Kansas

Date Well Completed: January 9, 2008

Plugging Commenced: January 9, 2008

Plugging Completed: January 9, 2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Water	0	225'	8 5/8"	225'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Used a total of 215 sacks to plug well - 60-40 Poz, 4% Gel, & 1/2# Flow Seal per sack. 1st Plug set @3510' with 25 sxs, 2nd Plug set @ 1370' with 25 sxs, 3rd Plug set @ 790' with 100 sxs, 4th Plug set @ 266' with 40 sxs - Bottom of Surface pipe, 5th Plug set @ 40' with 10 sxs, & Rathole with 15 sxs.

American Eagle Drilling LLC KCCPT per CP2/3

Name of Plugging Contractor: Allied Cementing Company, LLC License #: 33493


Address: P.O. Box 31 Russell, Kansas 67665

Name of Party Responsible for Plugging Fees: The Bill Bowman Oil Company (William "Bill" Bowman)

State of Kansas County, Rooks, ss.

William "Bill" Bowman (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) William "Bill" Bowman

(Address) 2640 W Road Natoma, Kansas 67651

SUBSCRIBED and SWORN TO before me this 28th day of January, 2008

Jackie J. Langholz My Commission Expires: 2-24-09
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 206, Topeka, Kansas 67202

RECEIVED
JAN 29 2008
KCC WICHITA

[Handwritten signature]