

15-163-19238-00-00.

Mailed Well Log Bureau

12-20-46

ALKAY OIL COMPANY

Westhusin No.1
NE-SE-NE Sec. 11-9S-17W
Rooks County
Kansas

2026 D.F.

Commenced: 6-14-46
Completed: 12-6-46
I.P. 80 barrels

0 - 50	Clay
50 - 90	Lime
90 - 722	Shale & shells
722 - 750	Sand & shale
750 - 780	Shale
780 - 938	Sand & shale
938 - 1105	Red rock & sand
1105 - 1284	Red rock & shells
1284 - 1314	Anhydrite
1314 - 1510	Red rock & shale
1510 - 1665	Salt & red rock
1665 - 1845	Shale
1845 - 1865	Anhydrite
1865 - 1955	Shale & shells
1955 - 2160	Sandy lime & shale
2160 - 2215	Sandy lime
2215 - 2310	Sandy Lime & shale
2310 - 2340	Lime & shale
2340 - 2367	Shale
2367 - 2380	Lime
2380 - 2896	Lime & shale Topeka @ 2896'
2896 - 2912	Lime gray
2912 - 2926	Lime - soft, white, porous
2926 - 2938	Lime
2938 - 2947	Lime, good saturation
2947 - 2983	Lime
2983 - 2989	Lime, white, soft
2989 - 2998	Lime - gray, chert
2998 - 3041	Lime
3041 - 3046	Lime - white, slight saturation & porosity
3046 - 3057	Lime-hard
3057 - 3064	Lime - soft, slight saturation
3064 - 3081	Lime & chert
3081 - 3086	Lime - white, soft, slight saturation - spotted
3086 - 3116	Lime - gray, hard
3116 - 3126	Red rock & shale Dodge @ 3126'
3126 - 3141	Lime - white, fair saturation - poor porosity
3141 - 3149	Shale, red & blue K.C. @ 3149'
3149 - 3153	Lime - gray, slight saturation spotted
3153 - 3169	Lime
3169 - 3172	Lime, slight saturation
3172 - 3191	Lime & shale
3191 - 3196	Lime, some saturation
3196 - 3209	Lime - hard
3209 - 3214	Lime - hard, fair saturation
3214 - 3217	Lime
3217 - 3224	Lime, moderately hard, fair saturation
3224 - 3236	Lime - gray, hard
3236	Total Depth. Rotary

3149
2026
-7123

3141
11:15

3141
3:25
11:15

RECEIVED
REGISTRATION COMMISSION
3-25-1988
MAR 25 1988

Cemented off with 100 sacks. Drilled out to 3227'. Set overnight with 3 bailers water & 1 bailer oil.

Drilled deeper - Cable tools

3236 - 3255	Lime & shale
3255 - 3257	Lime - soft, show of oil & water
3257	Total Depth
3233	P.B.

Acidized with 4400 gallons

Casing Record
8 5/8" - 1293'
5 1/2" - 3209'

REGISTRATION DIVISION
West. Kansas