

**KANSAS DRILLERS LOG**

API No. 15 — 065 — 20,712 — 00-00  
 County Number

S. 11 T. 9S R. 22 E  
 W

Loc. N/2 NW/4 NW/4

County GRAHAM

Operator  
 C-G DRILLING CO & H ROSEN OIL CO

Address  
 1107 UNION NATIONAL BUILDING, WICHITA, KS. 67202

Well No. 1 Lease Name VAN LOENEN


Footage Location  
 330 feet from (N) ~~XX~~ line 660 feet from (E) (W) line

Principal Contractor C-G DRILLING CO. Geologist FRANCIS WHISLER

Spud Date SEPTEMBER 14, 1974 Total Depth 3640' P.B.T.D.

Date Completed Oil Purchaser

640 Acres  
 N



Elev.: Gr. \_\_\_\_\_

DF \_\_\_\_\_ KB 2199

**CASING RECORD**

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE	12 1/4"	8 5/8"	20 & 32#	207.22'	COMMON	160	2% GEL 3% CA CL

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

**TUBING RECORD**

Size	Setting depth	Packer set at

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated

RECEIVED  
 STATE CORPORATION COMMISSION

OCT 4 1974

CONSERVATION DIVISION  
 Wichita, Kansas

16-4-74

**INITIAL PRODUCTION**

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator  
DANE G HANSEN TRUST

DESIGNATE TYPE OF COMP.: OIL, GAS,  
DRY HOLE, SWDW, ETC.:  
OIL

Well No. 1  
Lease Name VAN LOENEN

S 11 T 9 S R 22 E  
West

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
SHALE	0	1145		
SHALE & SAND	1145	1726		
ANHYDRITE	1726	1757		
SHALE	1757	2100		
LIME & SHALE	2100	2155		
SHALE & SHELLS	2155	2215		
LIME & SHALE	2215	3450		
LIME	3450	3640		
RTD		3640		

DST #1 3460'-3485'  
 OPEN 30 SI 30 OPEN 30 SI 30  
 REC 960' MUDDY SALT WATER  
 IBHP 1019#, FBHP 1019#  
 IFP 43#, FFP 480#  
 DST #2 3600'-3640'  
 OPEN 30 SI 30 OPEN 30 SI 30  
 REC 490' MUDDY SALT WATER  
 IBHP 1274#, FBHP 1263#,  
 IFP 65#, FFP 272#

STATE OF KANSAS )  
 COUNTY OF SEDGWICK ) ss

Subscribed and sworn to before me this  
 26th day of September, 1974.  
 My commission expires 12/7/75

*Phyllis Buchanan*  
 Notary Public

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

*D J Gallivan*  
 Signature  
 Partner  
 Title  
 September 26, 1974  
 Date

