

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Graham SEC. 36 TWP. 9S RGE. 22 /E/W
Location as in quarters or footage from lines:
NE SE NW

Locate Well
correctly on above
Section Platt.

Lease Owner Sandlin Oil Corporation
Lease Name Gustafson Well No. 1
Office Address 2300 Security Life Bldg., Denver, CO 80202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 7-1-83
Application for plugging filed 7-1-83
Plugging commenced 7-1-83
Plugging completed 7-2-83
Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ed Shoemaker
Producing formation _____ Depth to top _____ bottom _____ T.D. 3968'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	247'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud laden fluid @ 3968' - 3953'
20 sks cement @ 3953'
20 sks cement @ 1828'
100 sks cement @ 1086'
40 sks cement @ 300'
10 sks cement @ 40'
10 sks cement in rathole.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Emphasis Oil Operations

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Joe K. Branum (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe K. Branum
P. O. Box 506, Russell, KS 67665-0506
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of July, 19 83



Glenda R. Tiffin
Glenda R. Tiffin, Notary Public.
STATE CORPORATION COMMISSION
7-8-83
JUL 08 1983

My Commission expires: February 6, 1984.

EMPHASIS OIL OPERATIONS
P. O. Box 506
Russell, Kansas 67665-0506

DRILLERS LOG

OPERATOR: Sandlin Oil Corporation
2300 Security Life Bldg.
Denver, Colorado 80202

CONTRACTOR: Emphasis Oil Operations
P. O. Box 506
Russell, Kansas 67665-0506

LEASE: Gustafson WELL: #1

LOCATION: NE SE NW
Section 36-9S-22W
Graham County, Kansas

Total Depth: 3968'

Elevation:

Commenced: 6-24-83

Date Completed: 7-2-83

Casing: 8-5/8" @ 247' with 160 sks cement

Status: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil & Sand	30'	Anhydrite	1860'
Sand & Shale	253'	Sand & Shale	2600'
Sand, Shale & Iron Pyrite	1250'	Shale	3502'
Sand & Shale	1818'	Lime (R.T.D.)	3968'


RECEIVED
STATE CORPORATION COMMISSION

JUL 08 1983

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)


Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.




Joe K. Branum

Subscribed and sworn to before me this 7th day of July, 1983.

My Commission Expires: February 6, 1984.





Notary Public