

15-065-21708-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Graham SEC. 36 TWP. 9s RGE. 22 E/W
Location as in quarters or footage from lines:
330' FSL 2310 FEL

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

Lease Owner Eagle Explorations, Inc.
Lease Name Farrell Well No. #1
Office Address Suite 300, 107 N. Market Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 10-31-82
Application for plugging filed 10-31-82
Plugging commenced 10-31-82
Plugging completed 11-01-82
Reason for abandonment of well or producing formation No oil or gas shows

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Butcher

Producing formation _____ Depth to top _____ bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

| Formation | Content | From | To | Size | Put in | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| Surface | | | | 8 5/8" | 255' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- Plug #1 20 Saxes @ 3960' to 3879'
- Plug #2 20 Saxes @ 1870' to 1789'
- Plug #3 100 Saxes @ 1025' to 618'
- Plug #4 40 Saxes @ 260' to 98'
- Plug #5 10 Saxes & Wooden Bridge Plug @ 40' to Surface
- 5 Saxes in Rat Hole and 5 saxes in Mouse Hole

RECEIVED
STATE CORPORATION COMMISSION
11-16-82
NOV 16 1982
CONSERVATION DIVISION
Wichita, Kansas

Cement used ---50:50 Pozmix, 6% Gel, 3% CaCl₂
Total : 200 Saxes used.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____

STATE OF Kansas COUNTY OF Sedgwick, ss.
Carl Durr (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Carl Durr Carl Durr

(Address)

SUBSCRIBED AND SWORN TO before-me this 11th day of NOVEMBER 19 82

Jeff T. Logan
Notary Public.

My Commission expires:

