

15-173-02074-00-02

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

Sedgwick

County. Sec. 19 Twp. 27S. Rge. 2 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW SE

Lease Owner Abe Stekoll Oil Co

Lease Name Trustee Well No. I. A.

Office Address Box 944 Tulsa Okla.

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced Nov 27 1953 19

Plugging completed Dec 9 1953 19

Reason for abandonment of well or producing formation
not Producing Commercial quantity of oil

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Rural Durkee

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top 2944 ft Bottom 2945 Total Depth of Well 2945 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5 1/2 In	2944 ft	2058 ft
				10 "	105 ft	Left in.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Total Depth 2945 ft.
Filled with sand to 2935 ft
Dumped 6 sacks cement on sand,
Mud to 110 ft
10 ft rock bridge, Dumped 20 sacks cement on rock bridge,
Cement on rock bridge,
Mud to 10 ft.
5 ft rock bridge, Dumped 5 sacks cement on bridge
Filled to surface.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Abe Stekoll oil Co

Address P.O. Box 944 Tulsa Okla.

STATE OF Oklahoma COUNTY OF Tulsa, ss.

A. M. Stekoll

(employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

A. M. Stekoll

Box 944 - Tulsa, Okla

(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of December, 1953


My commission expires

8/24/54

Margaret

Notary Public.

28-3278-s 4-50-10M



Received 12/23/53

15-173-02074-00-00

DRILLER H J Uhl
LEASE OWNER- Abe Stekoll Oil Co

WELL - Trustee #1A
NW Se
Sec. 19-27S-2E
Sedgwick Co Kans

Commenced 8-8-51
Completed 8-20-51 with Rotary Tools

(Also known as Trustee #13)

Cemented 105' 10" Surface Pipe

FORMATION	FROM	TO
Shale and lime	105'	510'
Lime, shale and sand	510'	640'
Lime and shale	640'	790'
Shells and shale	790'	1021'
Shale and lime shells	1021'	1240'
Shale and lime	1240'	1380'
Lime and shale	1380'	1910'
Shale and lime	1910'	1990'
Shells and shale	1990'	2125'
Lime	2125'	2205'
Shale and lime	2205'	2270'
Lime and shale	2270'	2319'
Shale	2319'	2405'
Shale and lime shells	2405'	2475'
Lime	2475'	2530'
Lime and shale	2530'	2548'
Lime	2548'	2630'
Lime and shale	2630'	2650'
Shale and lime	2650'	2815'
Shale, Lime and shells	2815'	2870'
Shells and shale	2870'	2900'
Shale and lime	2900'	2945'

5 1/2" pipe cemented at 2944'

TOTAL DEPTH 2945'

Cemented

A F F I D A V I T

STATE OF Kansas)
COUNTY OF Sedgwick) ss

I, Fred Maddox of the H. J. Uhl Drilling Company, being first duly sworn on oath, state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Subscribed and sworn to before me this 3rd day of May, 1952.

Fred Maddox

My Commission Expires 4-28-56

Rva Tindle
Notary Public

PLUGGING
FILE SEC 19 T 27 R 2E
PAGE 133 LINE 35