


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Sedgwick County. Sec. 14 Twp. 26S Rge 2E (E) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Dundee Oil & Supply Co.
Lease Name Rose Hamant Well No 2
Office Address Box 923, Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed 11-9-1932 19____
Application for plugging filed 2-22-1957 19____
Application for plugging approved _____ 19____
Plugging commenced _____ 19____
Plugging completed April 10 19 57
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				15 1/2"	188'	none
				12 1/2"	1375	290'
				10"	1424	1425
				8 1/2"	2854	2300
				7"	3100	2900

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped 6 sacks of cement at 3050'. Shot pipe off at 2351'. Pulled pipe and mudded hole to 180'. Set rock bridge and dumped 40 sacks of cement. Finished mudding hole and dumped 10 sacks of cement at base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF Kansas COUNTY OF Reno, ss.
Employee (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. R. #1, Hutchinson, Kans.

R. R. #1, Hutchinson, Kans. (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of April, 19 57

My commission expires August 12, 1957

Notary Public.

PLUGGING
FILE SEC 14 T 26 R 2E
BOOK PAGE 142 LINE 20

4/18/57
CONSERVATION DIVISION
STATE CORPORATION COMMISSION

WELL RECORD

WELL NO. 7 LEASE Rose Mamant COMPANY Gypsy Oil Company AUTH. K-1497

DATE—Drilling Began 9-15-32 Well Completed 11-9-32 First Production 10-17-32
 Not

SHOT—Date Shot With Quarts—From To By

SAND RECORD Simpson Dolomite - 3151' to 3156' TOTAL DEPTH 3156'

INITIAL PRODUCTION* "P" 509.00 bbls. (11-27-32) + 10 water in 20 hrs.

CASING RECORD

S- 14 T-26S R- 2E

Size	Wt.	Thd.	Class	Make	Run	Sacks Cement	Pounds Cal. Chlo.	Pulled	Left In
15 1/2"	70	8	SH	Lapweld	188'	-	-	-	188'
12 1/2"	50	8	SH	Lapweld	1375	-	-	290	1085'
10"	40	8	SH	Lapweld	1425	-	-	1425	-
8 1/2"	32	10	SH	Seamless	2854	-	-	-	2854'
6-5/8"	24	10	SH	Seamless	3100	-	-	-	3100'
5-3/16"	20	10	SH	Seamless	76'-10"	(Liner set at 3151')		-	76'-10"

0									

Sedgwick County, Kans.

(* Best Day; "F", Flowing Naturally; "L", Air-Gas Lift; "S", Swabbing; "P", Pumping. Elevation - 1368'

ACIDIZED: 4/26/35 with 1000 gallons of 50% acid solution
 PRODUCTION: Before, 53 oil, 110 water --- After, 177 oil, 451 water

- December 23, 1932 Recovered all of 10" casing, tried to pull 12-1/2" casing and same parted 15 joints down.
- December 25, 1932 Ran overshot spear on 10" casing and fished for 12-1/2" casing, took hold but pulled off slips, failed to recover any more 12-1/2" casing. (1085' left in hole)

PLUGGING

FILE SEC 14 T. 26 R. 2E

BOOK PAGE 142 LINE 20

RECEIVED

STATE CORPORATION COMMISSION

FEB 1 1935

CONSERVATION DIVISION