


15-173-03651-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sedgwick County. Sec. 14 Twp. 26 Rge. 2 (E).....(W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW SW NE
Lease Owner John P. Gaty
Lease Name Borg Well No. 1
Office Address 6600 E. Central
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed Nov. 15 19 49
Application for plugging filed Nov. 15 7 19 49
Application for plugging approved Nov. 15 7 19 49
Plugging commenced Nov. 15 19 49
Plugging completed Nov. 15 19 49
Reason for abandonment of well or producing formation Hole full of water

If a producing well is abandoned, date of last production..... 19.....
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dwight Lilly
Producing formation Arbuckle Depth to top 3338 Bottom 3348 Total Depth of Well 3348 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
<u>Arbuckle</u>	<u>water</u>	<u>3338'</u>	<u>3348'</u>	<u>5"</u>	<u>3295 FT</u>	<u>1633 FT</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Mudded hole from 3348 back to 125 feet. Set fifteen foot rock bridge to 110. Ten sacks of cement on top of rock bridge. Mudded hole to surface. 2 sacks of cement on top.

REC'D
CORP
1/13/50
STATE
CORP

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....
Address.....

STATE OF....., COUNTY OF....., SS.

.....(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Max Howell
210 N. Edgemore Dr.
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of January, 19 50

My commission expires January 12, 1952
Berenice Kooker
Notary Public.

PLUGGING
NOV 14 7 26 AM '50
NOV 12 4 34 AM '50

WELL LOG - BORG #1

OPERATOR: J. P. Gaty
c/o Beech Aircraft Corp.
Wichita, Kansas

Location: NW SW NE
Section 14-268-2E
Sedgwick County, Kansas

CONTRACTOR: Morrison Drilling Company, Inc.
Drawer 712
El Dorado, Kansas

Production: _____

Farm: Borg Well No. 1

Date Commenced: October 26, 1949

Date Completed: November 7, 1949

Total Depth: 3295 feet

<u>From</u>	<u>To</u>	<u>Formation</u>
0	45	Clay
45	90	Shale and Lime Shells
90	205	Lime & Shale Breaks
205	210	Red Bed
210	270	Lime and Shale
270	280	Red Bed
280	385	Lime & Shale breaks
385	538	Lime and Shale
538	542	Red Bed
542	565	Lime and Shale
565	670	Lime and Shale breaks
670	940	Shale & Lime shells
940	950	Red Bed
950	970	Shale & Shells
970	985	Red Bed
985	1000	Shale & Lime Shells
1000	1005	Shale & Shells
1005	1010	Red Bed
1010	1089	Shale & Shells
1089	1098	Red Bed
1098	1325	Shale & Shells
1325	1370	Shale
1370	1920	Lime & Shale
1920	2085	Shale
2085	2093	Red Bed
2093	2225	Shale
2225	2302	Lime
2302	2323	Shale
2323	2345	Lime
2345	2362	Shale
2362	2370	Lime - Hard & Rough
2370	2376	Shale (Gyp)
2376	2397	Lime & Shale
2397	2585	Lime
2585	2600	Shale
2600	2625	Shale & Lime Breaks
2625	2830	Lime & Shale
2830	2845	Shale & Shells
2845	2900	Lime & Shale (Chirty)
2900	3154	Lime
3154	3185	Shale
3185	3247	Lime
3247	3260	Sand
3260	3295	Sand & Shale streaks
3295		Total Depth.

PLUGGING
FILE SEC 14-268-2E
BOOK PAGE 124 LINE 310

Cable Tool Log

Top of Arkuckle 3338


Total depth 3348 (no fluid)

Perforated casing from 3209-3213

Some free oil and sulphur water

WELL LOG - BORG #1 (Cont.)

I hereby certify that the foregoing is a true and correct copy of the Well Log for the Borg #1 Well drilled for Mr. J. P. Gaty and completed November 7, 1949.


C. W. Wilson
Secretary-Treasurer

STATE OF KANSAS }
COUNTY OF BUTLER } ss.

SUBSCRIBED AND SWORN TO, Before the undersigned, a Notary Public in and for the County and State aforesaid this 8th day of November, 1949.

My Commission Expires January 10, 1951


Notary Public