

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Sedgwick County, Sec. 3 Twp. 26 Rge. 2 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW NW

Lease Owner El Dorado Supply Company

Lease Name Feik Well No. 3

Office Address 764 Oil Hill Road, El Dorado, Kansas 67042

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 19 62

Application for plugging filed 8-7 19 72

Application for plugging approved 8-7 19 72

Plugging commenced 8-8 19 72

Plugging completed 8-11 19 72

Reason for abandonment of well or producing formation No Production

If a producing well is abandoned, date of last production June 19 72

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ted Dewey

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- 8-9-72 Plugged with rock 2135' to 2130'; mixed and dumped 6 sacks cement at 2130'. Ripped 7" casing at 2070';
- 8-10-72 Ripped and worked 7" casing at 2070'; pulled 51 joints.
- 8-11-72 Pulled 17 joints 7" casing; put in rock 220' to 200'. Cemented with 5 yds Ready-Mix 200' to 5'.

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1972
12-22-72
CONSERVATION DIVISION
Wichita, Kansas


Name of Plugging Contractor White & Ellis Drilling, Inc.
Address Box 448, El Dorado, Kansas 67042

STATE OF Kansas COUNTY OF Butler ss.
Ernest Sifford

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford

Subscribed and sworn to before me this 21st day of December 19 72



September 26, 1976

(Address) L. B. Auer Notary Public

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- HARVEST QUEEN MILL & ELEVATOR
Farm- Fpik No. 3

SEC. 3 T. 26 R. 2E
SW SW NW

Total Depth. 3637'
Comm. 3-21-62 Comp. 4-3-62
Shot or Treated.
Contractor. Canaday Drlg. Co.
Issued. 9-1-62

County Sedgwick
KANSAS



Elevation. 1378' RB

Production. 5 BOPD

CASING:

10 3/4" 200' w/200 sx cem.
7" 3435' w/90 sx cem.

Figures Indicate Bottom of Formations.

shale	160
lime	200
lime, shale	680
shale, lime	865
shale, shell	1180
shale, lime	1450
lime, shale	1635
shale, lime	2228
shale	2350
lime, shale	2475
shale	2482
lime	2640
lime, shale	2868
sand	2896
Mississippi lime	2915
lime	2990
lime, chert	3029
lime	3099
lime, chert	3166
lime	3175
shale	3230
lime	3305
sand, lime	3345
lime, sand	3428 RTD
No log	3637
Total Depth	

RECEIVED
STATE CORPORATION COMMISSION

AUG 8 1972

CONSERVATION DIVISION
Wichita, Kansas

TOPS: SCOUT	
Burgess	2882
Mississippi	2914
Kinderhook	3233
Hunton	3233
Simpson	3368
Arbuckle	3412