


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Sedgwick County. Sec. 3 Twp. 26 Rge. 2 (E) (W)  
Location as "NE/CNW/SW" or footage from lines SE SE NW  
Lease Owner El Dorado Supply Company  
Lease Name Feik  
Office Address 764 Oil Hill Road, El Dorado, Kansas 67042 Well No. 5  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed \_\_\_\_\_ 19 62  
Application for plugging filed 8-7 19 72  
Application for plugging approved 8-7 19 72  
Plugging commenced 8-12 19 72  
Plugging completed 8-16 19 72  
Reason for abandonment of well or producing formation No Production

If a producing well is abandoned, date of last production June 19 72  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ted Dewey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

- 8-12-72 Pulled wet string 2 1/2" tubing.
- 8-13-72 Finished pulling 2 1/2" tubing; started ripping 4 1/2" casing 2600' to 2300'. Plugged back with gravel to 2855'; mixed and dumped 5 sacks cement at 2855'.
- 8-15-72 Worked and ripped 4 1/2" casing 2300' to 1830'.
- 8-16-72 Finished pulling 4 1/2" casing; put up rock bridge 220' to 200'; cemented with 4 1/2 yds Ready-Mix 200' to 4'.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 22 1972  
12-22-72  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor White & Ellis Drilling, Inc.  
Address Box 448, El Dorado, Kansas 67042

STATE OF Kansas COUNTY OF Butler, ss.  
Ernest Sifford (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford

SWORN TO before me this 21st day of December, 19 72



(Address) L. B. Auer  
Notary Public.

September 26, 1972

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


COPY

Company- HARVEST QUEEN MILL & ELEVATOR CO.  
Farm- Feik No. 5

SEC. 3 T. 26 R. 2E  
SE SE NW

Total Depth. 2930'  
Comm. 12-9-62 Comp. 12-16-63  
Shot or Treated.  
Contractor. Canaday Drlg. Co.  
Issued. 3-2-63

County Sedgwick  
KANSAS



Elevation. Est. 1486' K.B.

Production. Pmp. 25 BOPD - NW

CASING:  
8 5/8" 202' w/170 sx cem.  
5 1/2" 2924' w/100 sx cem.

80 Figures Indicate Bottom of Formations.

shale	80
lime	155
lime, shale	606
shale, shells	945
shale, lime	1595
shale	1769
shale, lime	2215
shale	2280
lime	2365
shale, lime	2405
shale	2442
Kansas City lime	2507
shale	2640
shale, lime	2744
lime, shale	2855
shale, lime	2887
Burgess	2899
Mississippi	2930
Total Depth	

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 8 1972  
CONSERVATION DIVISION  
Wichita, Kansas

TOPS: SCOUT	SAMPLE
Burgess	2887
Mississippi	2899

# 3-330 - Salt water

H S.