

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 1972
6-6-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Draper of Dreiling Oil, Incorporated has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Dreiling Oil, Incorporated,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Farrell Well No. A-1

Location: NW-NW-SE Sec. 36 Twp. 9 Rge. (E)(W) 22

County: Graham Total Depth 3776' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Draper was instructed to plug the well as follows:

196'--8 5/8" Surface casing, cement circulated with 110 Sx.
Top of Dakota section @ 775'.

Circulate hole with heavy mud. Pull DP to 1000' and displace 110 Cu. Ft. cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10Cu. Ft. cement to bottom of cellar.

INVOICED

DATE _____
INV. NO. _____

Very truly yours,

W. L. Diebel
Conservation Division Agent