

15-065-20558-00-00

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 11 1972
7-11-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Burris of Chief Drlg. has this date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drlg. & Jet Drlg.

Complete Address: Suite 905 Century Plaza Wichita, Ks.

Lease Name: Gustafson Well No. 1

Location: SW SE NW Sec. 36 Twp. 9 Rge. (E)(W) 22

County: Graham Total Depth 3815' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Burris was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 900' and displace
70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

[Signature]
Conservation Division Agent