

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

12-7-79
R

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-163-20,206-00-00 (of this well)

Operator's Full Name ENERGY RESERVES GROUP, INC.

Complete Address 925 PATTON ROAD - GREAT BEND, KANSAS, 67530

Lease Name MEAS Well No. #2

Location SW-NW-5W Sec. 1 Twp. 10^S Rge. 17 (E) (W) W

County ROOKS Total Depth 3545 FE

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor HALLIBURTON SERVICES CO.

Address 1100 EAST 8TH ST. HAYS, MS. 67601 License No.

Operation Completed: Hour 10:30 AM Day 4TH Month DEC. Year 1979

The above well was plugged as follows:

8 5/8" 175 FE SP. CUC. w/150ST QUICK SET. -> 4 1/2 SET AT 3544 FE w/135ST
PLUG. BACK TO 3532 FE PERFS - 3170 FE TO 3172 FE -> 3228 FE TO 3234 FE
NO PIPE RECOVERY. -> 4 1/2 SQUEEZED AT 942 FE 1001 FE 2682 FE 2739 FE
ORDERED - 120ST HALLIBURTON LIGHT CMT. -> 12ST GEL -> 4ST HULL'S + 8 5/8" PLUG.
(PUMPED IN WITH PUMP TRUCK)

PMT IN 12ST GEL. - RELEASED PLUG. -> 100ST CMT WITH 4ST HULL'S MIXED IN.

MAX PRESSURE 400 LBS SHUT IN 150 LBS

PMT 20ST CMT. IN ANNULUS. - MAX PRESSURE 100 LBS SHUT IN 50 LBS

(CEMENTED BY HALLIBURTON)

I hereby certify that the above well was plugged as herein stated.

Signed: Marion J. Schmidt
Well Plugging Supervisor

INVOICED
DATE 12-7-79
INV. NO. 1052-w

DRILLERS LOG

15-163-20206-00-00

KEAS NO. 2

CASING RECORD:	OPERATOR:	Clinton Oil Company	DESCRIPTION:
8-5/8" @ 181' w/150 sax cement	CONTRACTOR:	Sage Drilling Co.	SW NW SW Sec. 1-10S-17W Rooks County, Kansas
TOTAL DEPTH: 3545'	COMMENCED:	May 7, 1969	
	COMPLETED:	May 18, 1969	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post Rock	0	60	
Shale & Shells	60	80	
Shale	80	182	
Shale & Shells	182	680	
Sand	680	918	
Red Bed	918	925	
Red Bed & Shale	925	1265	
Anhydrite	1265	1300	
Red Bed	1300	1439	
Shale & Shells	1439	1880	
Shale & Lime	1880	2635	
Lime & Shale	2635	2815	
Shale & Lime	2815	3070	
Lime & Shale	3070	3203	
Lime	3203	3545	4 1/2" @ 3544' w/135 sax

Plug back depth 3532'


I certify that this is a true and correct copy of the above log to the best of my knowledge.

RECEIVED
STATE CORPORATION COMMISSION
APR 19 1978
CONSERVATION DIVISION
Wichita, Kansas

SAGE DRILLING CO., INC.

T. M. McCaul, Jr.

By T. M. McCaul, Jr.



Subscribed and sworn to before me this 19th day of May, 1969.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.