

of
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-193-20011-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAR 17 1969
CONSERVATION DIVISION
Wichita, Kansas
03-17-1969

Operator's Full Name Trend Exploration, Limited,

Complete Address: 600 Capitol Life Building, Denver, Colorado.

Lease Name _____ Page _____ Well No. 1

Location GSW-SE Sec. 16 Twp. 9 Rge. (E) (W) 32

County Thomas Total Depth 1740'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Gabbert-Jones, Incorporated,

Address: 830 Sutton Place, Wichita, Kansas. License No. _____

Operation Completed: Hour 3:30 PM Day 13 Month 3 Year 1969

The Above well was plugged as follows:

278'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1550'.

Circulated hole with heavy mud. Pulled DP to 1775' and displaced 100 Sx. cement thru
DP from 1775' to 1450'. Pulled DP to 310' and displaced 20 Sx. cement thru DP from
310' to 250'. Pulled DP, set bridge @ 140' with 1/8 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/17/69
INV. NO. 9468-4

Signed: A. D. Dickels
Well Plugging Supervisor