

KANSAS

J
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1969
CONSERVATION DIVISION
Wichita, Kansas
12-22-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-193-20026-00-00

Operator's Full Name Trend Exploration, Limited,
Complete Address 600 Capital Life Building, Denver, Colorado.
Lease Name Nye Well No. 1
Location CNW-NW Sec. 16 Twp. 9 Rge. (E) (W) 32
County Thomas Total Depth 4688'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Gabbert-Jones, Incorporated,
Address 830 Sutton Place, Wichita, Kansas. License No.
Operation Completed: Hour 11:00 PM Day 16 Month 12 Year 1969

The above well was plugged as follows:

271'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1525'.

Circulated hole with heavy mud. Pulled DP to 1775' and displaced 100 Sx. cement thru
DP from 1775' to 1450'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from
310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 12/23/69
INV. NO. 1116-w