

15-193-00036-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 40-37

LOCATION NE NW NE

SEC. 30 TWP. 9 RGE. 32

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Herbel

Operator Westgate Greenland Oil Address Wichita, Kans

Field \_\_\_\_\_ County Thomas

Total Depth 5066 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 323' circulated with cement - 5 1/2" at 4556' with

100 sax cement behind, top perf. at 4472'.

Run plug to 4400', set rock, mud and 4 sax cement with dump

bailer, pulled 1750' 5 1/2", filled hole with mud to 300', set

rock bridge and 15 sax cement, filled with mud to 40', set rock

bridge and 10 sax cement to bottom cellar

RECEIVED  
STATE CORPORATION COMMISSION  
01-03-1951  
JAN X 3 1951

CONSERVATION DIVISION  
Wichita, Kansas

District Conservation Agent

Date 12-31-50

PLUGGING  
FILE SEC 30 T 9 R 32W  
BOOK PAGE 40 LINE 37