

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-163-20227-0600

RECEIVED
STATE CORPORATION COMMISSION

OCT 21 1974

CONSERVATION DIVISION
Wichita, Kansas

10-21-74

Operator's Full Name Tilco, Inc.

Complete Address 400 Century Plaza, Wichita, Kansas 67202

Lease Name Klim Well No. 3

Location SE SE NW Sec. 1 Twp. 10 Rge. (E) (W) 17

County Rooks Total Depth 3561'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Pipe Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 6 P Day 18 Month 10 Year 1974

The above well was plugged as follows:

Total depth 3561' 8 5/8 csg set at 209' cwc 150 sx.

5 1/2" csg set at 3559' cw 150 sx cem.

5 1/2" csg PBSD 3530' with perf. (3104-3191)

Set 5 1/2" wood plug at 3000' -poured 10' sd -dumped 4 sk cem W/dump bailer. (3000-2950)

Cutoff & recovered 2303' of 5 1/2" csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -70 sk poz 6% -

8 sk gel & water -released plug & pumped 50 sk cem by Allied.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/23/74

INV. NO. 155-W

Signed: Leo Z. Massey
Well Plugging Supervisor