

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-103-20233-00-00

RECEIVED
STATE CORPORATION COMMISSION
2-14-75
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Tilco, Inc.

Complete Address 400 Century Plaza, Wichita, Kansas 67202

Lease Name Klim Well No. 5

Location SE NW NW Sec. 1 Twp. 10 Rge. (E) (W) 17

County Rooks Total Depth 3545'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Pipe Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 5:15 P Day 12 Month 2 Year 1975

The above well was plugged as follows:

- Total Depth 3545' 8 5/8 csg set at 209' cwc 150 sk.
- 5 1/2 csg set at 3543' cw 150 sk cmt.
- Filled 5 1/2 csg W/sd (3545-3520) dumped 4 sk cmt W/dump bailer. (3520-3490)
- Cutoff & recovered 2222' of 5 1/2 csg.
- Mixed & pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -70 sk 50-50 poz
- 6% -8 sk gel & water -released plug & 50 sk 50-50 poz 6% by Allied Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Murray
Well Plugging Supervisor

INVOICED

DATE 2/13/75
INV. NO. 832-w