

 KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 13 1966  
10-13-1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-163-30220-00-00

Operator's Full Name National Associated Petroleum Company

Complete Address: 502 Ritz Building, Tulsa, Oklahoma

Lease Name Cecil Masters "C" Well No. 1

Location C SE NE Sec. 25 Twp. 10 Rge. 16 (E) (W) X

County Rooks Total Depth 3697'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Thoroughbred Drilling Company

Address: Tulsa, Okla., License No. \_\_\_\_\_

Operation Completed: Hour 4:15 P Day 11 Month 10 Year 1966

The Above well was plugged as follows:

Total Depth 3697' 8 5/8 csg set at 245' cwc 150 sc.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 25 sc

cement thru drill pipe. Heavy mud to 200' set cementing plug and displaced 20 sc cem-

ent thru drill pipe. Heavy mud to 40' set cementing plug, 1/3 sc hulls and 8 sc cement

to base of cellar. Plugged rat hole with 2 sc cement.

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed:   
Well Plugging Supervisor

DATE 10/13/66  
INV. NO. 4092-W