

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 163 - 20,802 - 00-00 (of this well)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 23 1978  
05-23-1978  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Rains & Williamson Oil Co., Inc.  
Complete Address 435 Page Ct., 220 W. Douglas, Wichita, Kansas  
Lease Name Nelson Well No. 1  
Location NW SW SW Sec. 27 Twp. 10 Rge. (E) (W) 16  
County Rooks Total Depth 3720  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Co. Tools  
Address        License No.       

Operation Completed: Hour 9:30 A Day 22 Month 5 Year 1978

The above well was plugged as follows:

RTD 3720' 8 5/8 csg set 200' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.  
Ganned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.  
Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Bob Massey  
Well Plugging Supervisor

DATE 5-23-78  
INV. NO. 7352.0