

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
NOV 25 1974
11-25-1974
CONSERVATION DIVISION
Wichita, Kansas

15-163-20396-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Lowell Pearson et al

Complete Address 314 Insurance Bldg., Wichita, Kansas 67202

Lease Name H.M. ^{KC} Nelson Well No. 1

Location N/2 N/2 SW Sec. 27 Twp. 10 Rge. (E) (W) 16

County Rooks Total Depth 3490'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Nicholos Casing Pulling

Address Box 373 Geneseo, Kansas 67444 License No. 711

Operation Completed: Hour 11:30 A Day 21 Month 11 Year 1974

The above well was plugged as follows:

- Total Depth 3490' 8 5/8 csg set at 169' cwc 125 sk.
- 5 1/2 csg set at 3480' cw 150 sk cem. & pfs (3470-3490)
- Filled 5 1/2 csg W/sd (3490-3450) dumped 4 sk cem W/dump bailer. (3450-3420)
- Cutoff & recovered 2909' of 5 1/2 csg.
- Pumped down 8 5/8 csg with 20 sk gel & water -100 lbs hulls -70 sk 50-50 poz 6% -
- 5 sk gel & water -released 8 5/8 plug & pumped 50 sk 50-50 poz 6%.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Z. Massey
Well Plugging Supervisor

DATE 11/25/74
INV. NO. 352-W