

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 1972
6-6-72
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dreiling Oil, Incorporated.
Complete Address R. R. #2, Victoria, Kansas.
Lease Name Farrell Well No. A-1
Location NW-NW-SE Sec. 36 Twp. 9 Rge. (E) (W) 22
County Graham Total Depth 3776'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 4:45 PM Day 4 Month 6 Year 1972

The above well was plugged as follows:

196'--8 5/8" Surface casing, cement circulated with 140 Sx.
Top of Dakota section @ 775'.

Circulated hole with heavy mud. Pulled DP to 1000' and displaced 110 Cu. Ft. cement
thru DP from 1000' to 675'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 6-6-72

INV. NO. 5805-W