

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 11 1972  
7-11-72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Chief Drilling & Jet Drilling

Complete Address Suite 905 Century Plaza Wichita, Kansas

Lease Name Gustafson Well No. 1

Location SW SE NW Sec. 36 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3815'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated     

Plugging Contractor Co. Tools

Address      License No.     

Operation Completed: Hour 4:30 P Day 9 Month 7 Year 1972

The above well was plugged as follows:

RTD 3815' 8 5/8 csg set at 225' cwc. Cmt. Mat. 50-50 poz cmt W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 900' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displace 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 9/11/72  
INV. NO. 6013-W

Signed: [Signature]  
Well Plugging Supervisor