

x 6-6

00-01-82
E-23,932

6 031266

API NUMBER 15- 179-20,276

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

E/2 SW SE, SEC. 18, T 8 S, R 26 W/EX

660 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Lease Name Taylor Well # 2

Operator: Kaiser Francis Oil Co.

County Sheridan 126.75

Name & Address Box 21468

Well Total Depth 3900 feet

Tulsa, Ok. 74121-1468

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 195

Abandoned Oil Well Gas Well Input Well X SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor B. J. Titan License Number

Address Oakley, Ks.

Company to plug at: Hour: PM Day: 6 Month: June Year: 19 89

Plugging proposal received from John Glenn

(company name) Kaiser Francis (phone)

were: 8 5/8" set at 195' cwc 165 sks. 5 1/2" set at 3899' w/150 sks. PBSD 3864'.

Perfs 3644' - 3830'. Perf at 1505' and cwc to surface w/1190 sks. Order 250 sks 65/35 poz

10% gel 500# hulls. B. J. Titan Cement Co. Wellbrock Water. Pulled full string/hole open.

Plugging Proposal Received by Carl Goodrow

(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 12:00PM Day: 6 Month: June Year: 19 89

ACTUAL PLUGGING REPORT Squeezed 5 1/2" casing w/250 sks cement blend w/500# hulls mixed

in last 100 sks to max psi 700#. Close in psi 600#. Plug completed.
Backside had cement showing.

RECEIVED
STATE CORPORATION COMMISSION
6-26-1989
JUN 26 1989

Remarks: (If additional description is necessary, use BACK of this form.)
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 6-27-89
INV. NO. 25127

Jib.S

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow