

6 040277

API NUMBER 15- 179-20,775 100-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SW NE, SEC. 20, T. 8 S, R. 26 WXX

3630 feet from (S) section line

1650 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5342

Lease Name Pratt Well # 1-20

Operator: Beacon Exploration Company

County Sheridan

Name & Address 410 17th St. Suite 2300

Well Total Depth 4411 143.36 feet

Denver, Co. 80202

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 218 w/200 sks

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling License Number 5422

Address Wichita, Ks.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Wilmer Dreiling

(company name) Abercrombie (phone) _____

were: Order 200 sks 50/50 pozmix 6% gel 3% cal. cl. 2 sk hulls and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plug sections with good

circulation and no fluid loss.

RECEIVED
STATE CORPORATION COMMISSION

DEC 17 1984

CONSERVATION DIVISION
Wichita, Kansas

12-17-84

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XX

Operations Completed: Hour: 12:45 AM Day: 30 Month: NOVEMBER Year: 19 84

ACTUAL PLUGGING REPORT

1st plug @ 2140 w/40 sks

2nd plug @ 1225 w/100 sks w/2 sks hulls

3rd plug @ 225 w/40 sks

4th plug @ 40 w/10 sks

10 sks in Rat Hole

Remarks:

(If additional description is necessary, use BACK of this form.)

(If did / did not) observe this plugging.

Signed Dennis L. Hamel
(TECHNICIAN)

DATE 12-84
INV. NO. 6257
11-30

FEB 19 1985
JAN 14 1985

12-13-84
33