

7-14

4-031843

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-20,314-00-01

SE SE NE /4 SEC. 23, 08 S, 26 W
2970 feet from S section line
330 feet from E section line

Operator license# 5474 Lease Pratt well # 1

Operator: Northern Lights Oil Company County Sheridan

Address: P.O. Box 164 Well total depth 3926 feet 127.59
Andover, Kansas 67002 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 245 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling License# 6050

Address: Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 14 Month: July Year: 93

Plugging proposal received from: Dave

Company: Kelso Casing Pulling Phone: _____

Were: Ordered 230 sxs. 65/35 pozmix - 10% gel. - 900# hulls.
Sand and common cement.
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 3:00P.M., Day: 14, Month: July, Year: 93

Actual plugging report: 8 5/8" set @ 245' sxs. cwc. 4 1/2" set @ 3925'
w/225 sxs. Perf. @ 3745' - 3884'. Sand back to 3700' w/4 sxs.
common cement on sand with bailer. Shot @ 2700' - 2000'. Mix and pump
cement slurry from 1350' to 2700' with 40 sxs. to 800#. Shot off @ 875'.
Mix and pump 125 sxs. cement blend and hulls to circulate. Lay down
4 1/2" casing, topped off with 25 sxs. Total 195 sxs. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1993
CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
Condition of casing(in hole): GOOD BAD Any plug: YES NO
Bottom plug(in place): YES NO CALC Dakota plug: YES NO
Plugged through TUBING _____, CASING . Elevation: _____ GL

I did not observe the plugging. Carl Goodrow

DATE SEP 02 1993
INV. NO. 38523

HO
(agent)
Form CP-2/3