

4-032162

API Number: 15-179-20,622 - 00-01

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

6-5

SW SE NW /4 SEC. 27, 08, 26 W
440 feet from S section line
440 feet from E section line

Operator license# 4767

Lease: Robben Well # P-4

Operator: Ritchie Exploration, Inc.

County: Sheridan

Address: 125 N. Market - Suite 1000
Wichita, Kansas 67202

Well total depth 3988 129.61 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 187 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing and Salvage License# 31529

Address: Chase, Kansas 675245

Company to plug at: Hour: P.M. Day: 5 Month: June Year: 1996

Plugging proposal received from: Richard

Company: Mike's Testing and Salvage Phone: -

Were: Order 200 sxs 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.
Order sand and common cement.

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 25 1996
6-25-1996
CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 2:30 P.M., Day: 5, Month: June, Year: 1996

Actual plugging report: 8 5/8" set at 187' cwc with 180 sxs. 5 1/2" set at 3982' with 200 sxs. Prod. Perfs. - 3747' - 3892'. PBSD 3968'. Sanded back to 3700' with 5 sxs common cement on sand with bailer. Shots at 2114' - 1730'. Recovered 1400' of 5 1/2" casing. Mixed and pumped down casing 125 sxs cement blend with 500# hulls mixed in. Pulled casing to 250'. Mixed and pumped 65 sxs cement blend to circulate. Pulled 5 1/2" casing topped off with 10 sxs cement blend. Used 200 sxs cement blend with 500# hulls. Plug complete.

Remarks: Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

INVOICED did not observe the plugging.

Carl Goodrow

(agent)

DATE JUN 26 1996
45885

Form CP-2/3