

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-179-20627-00-00  
Spot: E2E2NW Sec/Twnshp/Rge: 27-8S-26W  
3123 feet from S Section Line, 4268 feet from E Section Line  
Lease/Unit Name: ROBBEN P Well Number: 7  
County: SHERIDAN Total Vertical Depth: 3953 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: BOX 783188 8100 E 22ND ST. N. #700  
WICHITA, KS 67278

Production Casing Size: 5.5 feet: 3952  
Surface Casing Size: 8.625 feet: 206 175 SX CMT

175 SX CMT

*#128.47*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/15/2003 11:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: PETE FIORINI Company: RITCHIE EXPLORATION, INC. Phone: (785) 623-1506

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Plug thru tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 05/15/2003 2:30 PM KCC Agent: DARREL DIPMAN

**Actual Plugging Report:**  
Perforations 3871' - 3877'. PBSD 3952'. Casing leak at 1645'.  
8 5/8" S.P. at 206' w/175 sxs cement. 5 1/2" at 3952' - cement unknown.  
Ran tubing to 2091' - pumped 50 sxs cement with 200# hulls.  
Pulled tubing to 1267' - pumped 50 sxs cement with 200# hulls.  
Pulled tubing to 570' - pumped 40 sxs cement with 50# hulls - cement to surface.  
Connected to 5 1/2" casing - pumped 40 sxs cement.  
Max. P.S.I. 250#. S.I.P. 100#.  
Connected to 8 5/8" surface casing - pumped 110 sxs cement with 50# hulls.  
Max. P.S.I. 250#. S.I.P. 100#.  
Note: The scout card shows the location was measured from the SE corner of the NW/4.  
A GPS was used to pinpoint the well and Leo III was used to obtain the footage from the SE corner of the section.

**RECEIVED**  
**MAY 30 2003**  
**KCC WICHITA**

Remarks: LEASE ALSO KNOWN AS CATHERINE ROBBEN #7-27. ALLIED CEMENTING COMPANY.  
Plugged through: TBG

District: 04 Signed Darrel Dipman  
(TECHNICIAN)

MAY 21 2003

INVOICED  
5.30.03  
200 3061596

DON E PRATT

P.O. BOX 370

HAYS, KS 67601

CONTR MURFIN DRILLING CO

#7-27 CATHERINE ROBBEN

CTY SHERIDAN

27-8-26W

1320' FSL &

440' FEL, NW/4

GEOL

FIELD

STUDLEY SOUTH

E 2523 KB

CM 11/12/81

CARD

ISSUED 1/28/82

IP

OIL WELL

API 15-179-20,627

LANS 3871-3877

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
TOP	3410	- 887	
HEEB	3652	-1129	
TOR	3672	-1149	
KC	3693	-1170	
TD	3916	-1393	

8-5/8" 206/175sx; 5 1/2" 3952

DST (1) 3680-3748/30-30-30-30, REC  
720' FL (120' SOCM, 420' SOCMW, 180' W)  
SIP 1105-1069#, FP 76-227/276-  
387#

DST (2) 3750-85/30-30-60-30, REC 375'  
SW, SIP 944-913#, FP 55-101/133-  
173#

DST (3) 3801-64/30-30-60-30, 90' G,  
932' FL (2' CL GO, 480' OCW, 450' W)  
SIP 1218-1143#, FP 84-221/269-  
480#

MICT - CO, PF 24/3871-77, FU 1500'  
OIL, 12HRS, FU 2200', AC 2500 GAL,  
SWB 52 BOPH, 700' OB, POP, P EST 100+  
BOPC - 1/15/82

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

KCC

MAY 28 2003

HAYS, KS