

4-031977

8-31

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-20,663 -00-00
100'W.ofC.
E2 E2 SE /4 SEC. 27, 08 S, 26 W
1320 feet from S section line
440 feet from E section line

Operator license# 4767

Lease Robben "P" well # 14

Operator: Ritchie Exploration, Inc.

County Sheridan

Address: 125 N. Market
Suite #1000
Wichita, Kansas 67202

Well total depth 4000 feet 130.00
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 213 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing, Inc. License# 6050

Address: Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 31 Month: August Year: 94

Plugging proposal received from: Richard

Company: Kelso Casing, Inc. Phone:

Were: Order 200 sxs. 60/40 pozmix - 10% gel - 500# hulls
Allied Cement Company.
Order sand and common cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 14 1994
9-14-1994
CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 7:00P.M., Day: 31, Month: August, Year: 94

Actual plugging report: 8 5/8" set @ 213' w/140 sxs. cwc. 4 1/2" set @
3990' w/200 sxs. Prod. perms. 3896' - 3902'. P.B.T.D. 3974'.
Sanded back to 3846' w/4 sxs. common cement on sand with bailer.
Recovered 852'of casing with shots at 2100'-1800'-1100'-952'. Mixed and
pumped 100 sxs. cement blend with 200# hulls mixed in from surface to
2200'. Pulled casing to 200' circulated cement blend slurry with 100#
hulls mixed in to surface with 50 sxs. Pulled casing. Topped off with
20 sxs. cement blend slurry. Used total 170 sxs. cement blend with 300#
hulls. Plug complete.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did X did not [] observe the plugging. Carl Goodrow

INVOICED

DATE 9-26-94

INV. NO. 41264

(agent)
Form CP-2/3