

6 031221

1-17 15-179-20433-00-00
API NUMBER 15- NA

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SW SW, SEC. 23, T. 8 S, R 27 W/E
990 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Lease Name Taylor Well # 1

Operator: Beren
Name & Address: Box 723
Hays, Ks. 67601

County Sheridan 127.56

Well Total Depth 3925 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 284

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B. J. Titan License Number _____

Address Hays, Ks.

Company to plug at: Hour: PM Day: 17 Month: Jan Year: 19 89

Plugging proposal received from Bob Grant

(company name) Beren (phone) _____

were: 8 5/8" set at 284' w/175 sks. 4 1/2" set at 3924' w/150 sks. Perfs
3764' - 3886'. Order shots at 1950' and 1300'. Order 350 sks 65/35 Poz 10% Gel
2% Dixel 500# Hulls. B. J. Titan Cement Co. Joe Newman Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:15PM Day: 17 Month: Jan Year: 19 89

ACTUAL PLUGGING REPORT Squeezed 4 1/2" w/250 sks cement w/500# Hulls mixed in to max psi
800#. Close in 500#. Plug complete.

Squeezed 8 5/8" w/100 sks cement to max psi 400#. Close in psi 200#.

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1989 1/27/89

Remarks: (If additional description is necessary, use BACK of this report)

INVOICED
I did / I did not observe this plugging.

DATE 2-02-89
INV. NO. 23824
1-17

J.S.

Signed Carl Goodrow (TECHNICIAN)