

4-032102

10-19

API Number: 15-179-20,139 <sup>00-00</sup>

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

SE NW NE /4 SEC. 32, 08S, 29 W  
4290 feet from S section line  
1650 feet from E section line

Operator license# 32523 Lease: Koster Well # 3

Operator: Raney Oil Company County: Sheridan

Address: 3425 Tam O'Shanter  
Lawrence, Kansas 66047  
Well total depth 4130 <sup>134.23</sup> feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 7 Inch @ 210 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 19 Month: October Year: 1995

Plugging proposal received from: Roger Welty

Company: Phone:

Were: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 12:00 P.M., Day: 19, Month: October, Year: 1995

Actual plugging report: 7" set at 210' cwc with 200 sxs. 4 1/2" set at 4110' with 125sxs. O.H. at 4110' - 4130'. Holes squeezed in 4 1/2" previously and holes developed in critical control areas. Decision to plug. Squeezed 4 1/2" with 200 sxs cement blend with 450# hulls mixed into Max. P.S.I. 500#. Close in P.S.I. 150#. Squeezed 8 5/8" with 50 sxs cement blend with 50# hulls to Max. P.S.I. 150#. Close in P.S.I. 150#. Plug complete.

Remarks: Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO  
Plugged through TUBING, CASING. Elevation: GL

Individual [ ] observe the plugging.

Carl Goodrow (agent)

INVOICED

DATE 11-1-95

INCL. NO. 43921

10-19 JAN 17 1996

100

RECEIVED  
OCT 20 1995  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS

10-30-95