

347

To: 6 031391
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 179-20,960 -00-00
SW NE NE, SEC. 24, T 8 S, R 27 W/Ex

TECHNICIAN'S PLUGGING REPORT

Operator License # 5184

4290 feet from S section line
990 feet from E section line

Operator: Shields Oil Producers Inc.
Name & Address: Shields Bldg.
Russell, Ks. 67665

Lease Name Taylor Well # A-1
County Sheridan 127.73

Well Total Depth 3930 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 222

Abandoned Oil Well xx Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: AM Day: 17 Month: July Year: 19 90

Plugging proposal received from Vernon

(company name) Kelso (phone)

were: 8 5/8 set at 222 w/165 sks cwc. 4 1/2 set at 3917 w/125 sks. Perfs
3838 - 41. Order sand and common cement. Pull pipe. Order 250 sks
65/35 poz 8% gel 500 lbs. hulls. Allied Cement Co. LaRue Water Truck.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part xx None

Operations Completed: Hour: 9:00AM Day: 17 Month: July Year: 19 90

ACTUAL PLUGGING REPORT Sand back to 3800 w/4 sks common cement on
sand w/bailer. Rec. 2600. Sq 8 5/8 w/250 sks cement blend with hulls mixed into
max pres 500 lbs. Close in psi 300 lbs. Plug complete.

STATE CORPORATION COMMISSION

AUG - 7 1990
8-7-90
CONSERVATION DIVISION
Wichita, Kansas

Remarks:
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 15 1990

INV. NO. 2 8931

lib.S.

Signed Carl Goodrow
(TECHNICIAN)