

12-17-87 15-179-00161-00-01

6 031021

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1956.
NW NW NW SEC. 26, T 8 S, R 27 W/E

TECHNICIAN'S PLUGGING REPORT

4950 feet from S section line
4950 feet from E section line

Operator License # 5247

Lease Name Brown Well # A 1

Operator: Oil Property Management Inc.

County Sheridan 136.83

Name & Address 107 N. Market Suite 914

Well Total Depth 4210 feet

Wichita, Kansas 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 272

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number

Address R ssell, Kansas

Company to plug at: Hour: PM Day: 17 Month: Dec Year: 19 87

Plugging proposal received from Dean Ives

(company name) Oil Property Mng. (phone)

were: 8 5/8" set at 272' w/175 sks. 5 1/2" set at 4210' w/150 sks. PBDT 3986'.

Perfs 3883' - 3992'. Shots at 1800' BK and 2185' Anhy for block squeeze w/plug.

Order 250 sks ATL Cement Blend 65/35 Poz 10% Gel 2% Dical 5 sks Hulls. Allied

Cement Co. Joe Newman Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30PM Day: 17 Month: Dec Year: 19 87

ACTUAL PLUGGING REPORT Squeezed 5 1/2" casing w/180 sks Cement Blend w/5 sks Hulls mixed in to Max Psi 500#. Close in Psi 300#. Test backside to 500# cement at surface, from old squeeze. Plug complete.

1-18-88

RECEIVED STATE CORPORATION COMMISSION

JAN 18 1988

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-20-88

INV. NO. 19612

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow