

6030831

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-179-20,880-00-00

SE NW 1/4 SEC. 33, T. 8 S, R. 29 W

4290 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name K&L FARM well # 1

Operator: JOHN O. FARMER, INC.

County SHERIDAN 136.34

Name & Address P.O. Box 352

Well Total Depth 4195 feet

RUSSELL, KANSAS

Conductor Pipe: Size \_\_\_\_\_ feet

67665

Surface Casing: Size 8 5/8" feet 285'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor ALLIED CNT CO. License Number \_\_\_\_\_

Address RUSSELL KANSAS

Company to plug at: Hour: AM Day: 15 Month: 12 Year: 19 86

Plugging proposal received from GIB AUGUSTINE

(company name) JOHN O FARMER (phone) \_\_\_\_\_

were: 8 5/8" SET @ 285' w/ 165 SX CIRC. HOLE FROM BOTTOM TO TOP

MAINTAIN FLUID LEVEL @ SURFACE w/ NO LESS THAN 36 UIS MUD

ORDER 190 SX. 60/40 POZ 6% GEL 3% CC 8 5/8" W.P. ALLIED CNT. CO.

CEMENT THROUGH DRILL PIPE. BALLANCE PLUGS w/ MUD.

LOSS OF CIRC. @ 2186 (CH) WAS CEMENTED OFF. WHILE DRILLING

Plugging Proposal Received by Carl Goodnow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 7:30 AM Day: 15 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT SPOT D.P. @ 2475' DISPLACE 25 SX. CNT. MIX

LAYDOWN D.P. TO 1550' DISPLACE 100 SX. CNT MIX + 1 SX. HULLS

LAYDOWN D.P. TO 330' DISPLACE 40 SX. CNT. MIX LAYDOWN D.P.

ADJUST FLUID LEVEL IN HOLE TO 40' PUSH W.P. TO 40" FILL

HOLE TO BASE OF CELLAR w/ 10 SX. CNT. MIX. DISPLACE w/ JOINT OF PIPE

15 SX. IN RAT HOLE 10 SX IN MOUSE HOLE TO PLOW DEPTH.

Remarks: ELEV. 2837 KB ANHY 2452-89

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas  
DEC 19 1986  
12-19-86

INVOICED

DATE 12-31-86

Signed Carl Goodnow  
(TECHNICIAN)

INV. NO. 15690