

6 050336

APR 29 1987  
API NUMBER 15- 179 20 891 -00-00

To:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

N/2 NW NW, SEC. 33, T 8 S, R 29 W/E  
4950 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Lease Name Reitcheck Well # 1

Operator: L. D. Drilling

County Sheridan 135.69

Name & Address: Box 183 B

Well Total Depth 4175 feet

Great Bend, Ks.

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 293

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Lobo Drilling License Number 5864

Address

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Irwin Neighbors

(company name) Lobo Drilling Co. (phone)

were: Order 200 sks 60/40 Pozmix 6% Gel, 1 sk. Floccel and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Elev. 2795 - 1500 = 1295 + 300 = 1595

Anhy, 2448 to 2484 No Arb.

Plugging Proposal Received by Gilbert Leiker (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:00 PM Day: 29 Month: April Year: 19 87

ACTUAL PLUGGING REPORT

1st plug at 2460 w 25 sks.

2nd plug at 1620 w/110 sks. 1sk Floccel

3rd plug at 340 w/40 sks.

4th plug at 40 w/ 8 5/8 Plug. and 10 sks.

Cemented by Allied

Remarks: 15 sks. in rat hole. No mouse hole. additional description is necessary, use BACK of this form.)

INVOICED

(did not) observe this plugging.

DATE 6-2-87

Signed Gilbert P. Leiker (TECHNICIAN)

INV. NO. 17101

Gilbert P. Leiker

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas  
6-1-87