

To: 6 031578
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-31
API NUMBER 15- 179-20,081-00-01

SE. NE. NE., SEC. 34, T. 8 S, R. 29 (W) E
4290 feet from S section line
330 feet from E section line
Flood

TECHNICIAN'S PLUGGING REPORT

Operator License # 6477

Lease Name West Hoxie Well # M-2

Operator: Koch Exploration
Name & Address: P.O. Box 2256
Wichita, Kansas 67201

County Sheridan 137.18
Well Total Depth 4221 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 226'

Abandoned Oil Well _____ Gas Well _____ Input Well SWD Well D&A _____

Other well as hereinafter indicated C-18,370 E-18,370

Plugging Contractor Halliburton Services License Number _____

Address Oberlin, Kansas

Company to plug at: Hour: A.M. Day: 31 Month: 7 Year: 19 91

Plugging proposal received from Laverne Leiker

(company name) Koch Exploration (phone) _____

were: 8 5/8 set @ 226' w/180 sx. cwc. 4 1/2 set @ 4219' w/200 sx. PBD 4190' @ 3200'.

Squeezed @ 2900'. Perfs. 3930' - 4172'. Order 325 sx. 65/35 poz. 10% gel. 500# hulls.

Halliburton Services. Hoxie Tank Service Water. Pulled tubing and packer. Hole

open across perfs. Shots @ 2450' and 1600'.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 A.M. Day: 31 Month: 7 Year: 19 91

ACTUAL PLUGGING REPORT Squeezed 4 1/2 w/225 sx. cement blend w/hulls mixed in last 100 sx.

To max. P.S.I. 1000#. Close in 400#. Squeezed 8 5/8 w/100 sx. cement blend to

max. P.S.I. 250#. Close in P.S.I. 150#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

I (do not) observe this plugging.

INVOICED
DATE 10-4-91
INV. NO. 33249

Lib. S.

Signed Carl Goodrow (TECHNICIAN)

RECEIVED
OCT 01 1991
CONSERVATION DIVISION
WICHITA, KANSAS