

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Bulldog Pipe & Supply
Complete Address 612 Mayo Building, Tulsa, Oklahoma 74103
Lease Name Sanford Well No. 2
Location SW-NE-NW Sec. 5 Twp. 8 Rge. (E) (W)22
County Graham Total Depth 3792'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Forbes Casing Pulling Company, Incorporated.
Address Box #221, Great Bend, Kansas. License No. 637
Operation Completed: Hour 1:00 PM Day 10 Month 1 Year 1970

The above well was plugged as follows:

223'--8 5/8" Surface casing, cement circulated with 175 Sx.
3791'--5 1/2" Production casing cemented on bottom with 140 Sx. Well plugged back to
3559'. Top perforations from 3554' to 3549'.
Sanded well back to 3525' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
and squeezed well initially with 5 sacks hulls and 21 sacks gel then 100 Sx. cement
from 900' to 575', then 8 sacks gel from 575' to 250' and followed with 25 Sx.
cement from 250' to 175' then 4 sacks gel from 175' to 30' and finally 10 Sx. cement
from 30' to bottom of cellar. Maximum pressure-300#. Final shut-in pressure-150#.
(mudding and cementing operations by Allied Cementing Company, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 1/15/70
INV. NO. 1248-u

Signed: N. L. Nichols
Well Plugging Supervisor