

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name F & M Oil Company,

Complete Address 605 Union Center, Wichita, Kansas.

Lease Name Buckner Well No. 1

Location NW-SE-NE Sec. 1 Twp. 8 Rge. (E) (W) 22

County Graham Total Depth 3654'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor B & B Drilling, Incorporated,

Address 720 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 7:00 PM Day 19 Month 10 Year 1971

The above well was plugged as follows:

206'--8 5/8" Surface casing, cement circulated with 145 Sx.
Top of Dakota section @ 600'.

Circulated hole with heavy mud. Pulled DP to 825' and displaced 100 Sx. cement thru
DP from 825' to 500'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. S. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/22/71

INV. NO. 4579-W