

15-065-01314-00-01

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 15 1970  
CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Bulldog Pipe & Supply

Complete Address 612 Mayo Bldg., Tulsa, Oklahoma 74103

Lease Name Sanford Well No. 3

Location NE-NW-NW Sec. 5 Twp. 8 Rge. (E) (W) 22

County Graham Total Depth 3812'

Abandoned Oil Well        Gas Well        Input Well        SWD Well X D & A       

Other well as hereafter indicated       

Plugging Contractor Forbes Casing Pulling Company, Incorporated,

Address Box #221, Great Bend, Kansas, License No. 637

Operation Completed: Hour 12:30 PM Day 12 Month 1 Year 1970

The above well was plugged as follows:

207'--8 5/8" Surface casing, cement circulated with 150 Sx.

3654'--5 1/2" casing cemented on bottom with 125 Sx. Well plugged back to 3400'. Top perforations @ 3331'.

Pushed plug to 3325', sanded to 3300' and set 5 Sx. cement with dump bailer. Pulled

5 1/2" casing and squeezed well initially with 5 sacks hulls and 21 sacks gel and follow-

ed with 100 Sx. cement from 900' to 575', then 8 sacks gel from 575' to 250' and follow-

ed with 25 Sx. cement from 250' to 175' then 4 sacks gel from 175' to 30' and finally

10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure-200#. Final

shut-in pressure-100#. (Mudding and cementing operations by Allied Cementing, Inc.,).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols  
Well Plugging SupervisorDATE 1/15/70  
INV. NO. 1249-W