

DISTRICT CONSERVATION AGENT'S REPORT

15-065-00246-00-00

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW NW SE

SEC. 20 TWP. 8 RGE. 22W

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Moore

Operator Deep Rock Oil Corp Address Hutchinson, Kans

Field _____ County Graham

Total Depth 3925 Feet.

(Describe briefly the manner in which the well was plugged)

8 3/8" at 114' circulated with cement,
Circulated hole with heavy mud, spotted 18 sax cement on bottom
through drill pipe, pushed cementing plug to 3670' spotted 75 sax
cement through drill pipe 3670' to 3424' - Heavy mud to 125',
set cementing plug at 125', spotted 20 sax cement through drill
pipe at 125', filled with mud to 40', set cementing plug, 1/2 sack
hulls and 10 sax cement to bottom cellar.

Cementing by Halliburton Co .

11-16-51

RECEIVED
STATE CORPORATION COMMISSION

NOV 16 1951

CONSERVATION DIVISION
Wichita, Kansas

Edo Teer
District Conservation Agent

Date 11-9-51

PLUGGING
FILE SEC 20 TWP 8 RGE 22W
BOOK PAGE 124 LINE 35

X